DELTA DESIGN
INC.

3900

INSTRUCTION MANUAL

DELTA DESIGN, INC.
5775 Kearny Villa Rd.
San Diego, California 92123
(714) 292-5000
TWX: (910) 335-1215

INSTRUCTION MANUAL
Model 3900



DELTA DESIGN
INC.

ENVIRONMENTAL TEST CHAMBER

ENVIRONMENTAL CONTROL EQUIPMENT FOR RESEARCH AND INDUSTRY
5725 KEARNY VILLA ROAD • SAN DIEGO, CALIFORNIA 92123

Don OsThiemer

3900-0980

Printed in U.S.A.

PROPRIETARY NOTICE

The information and design disclosed herein were originated by and are the property of Delta Design, Inc.—Delta Design, Inc. reserves all patent, proprietary design, manufacturing, reproduction use, and sales rights thereto, and to any article disclosed therein, except to the extent rights are expressly granted to others. The foregoing does not apply to vendor proprietary parts.

Specifications remain subject to change to allow the introduction of design improvements.

Copyright 1980©
Delta Design, Inc.
5725 Kearny Villa Rd.
San Diego, CA 92123

Printed in U.S.A.

SPECIFICATIONS

TEST VOLUME (H x W x D)	10" x 16" x 10" (25.40$_3$x 40.64$_3$x 25.40 Cm) .92 FT^3 (.026M^3)
AIR CIRCULATION	Two 140 CFM Centrifugal Blowers With Baffling To Provide Equal Distribution Throughout The Chamber. The Air Flow Is In A Vertical Pattern.
OUTSIDE CASE DIMENSIONS (H x W x D)	17-7/8" x 27-1/2" x 24" (46.40 x 69.85 x 60.96 Cm)
INNER LINER	Type 302 Stainless Steel
OUTER CASE	Aluminum
INSULATION	Fiberglas
WEIGHT	90 Lbs (40.82 Kg)
POWER REQUIREMENTS	120 VAC, 50/60 Hz, Single Phase, 1875 Watts or 240 Vac, 50/60 Hz, Single Phase, 1875 Watts
CONTROLS	POWER On-Off Switch and Light COOL On-Off Switch and Light HEAT On-Off Switch and Light TEMPERATURE SET Control MANUAL/PROGRAM Control Switch (MODE)
HEATING ELEMENTS	Four 8.75 Ohm Elements, Total Of 1,775 Watts, Nichrome Wire
COOLING	Liquid Carbon Dioxide (LCO_2) or Liquid Nitrogen (LN_2)
PROGRAMMING	Programmable
COOL DOWN TIME	Ambient to -54°C in 2-3/4 minutes
HEAT UP TIME	Ambient to +217°C in 15 minutes
TEMPERATURE RANGE	-73°C to +315°C
RESETTABILITY	±0.25°C
TEMPERATURE DEVIATION	±0.1°C

LINE VOLTAGE STABILIZATION	±0.25°C For 105 to 125 VAC Line Voltage Change ±0.25°C For 220 to 240 VAC Line Voltage Change
AMBIENT TEMPERATURE COMPENSATION	±0.010°C/°C
HEAT LOAD COMPENSATION	±0.040°C/Watt
GRADIENT IN TEST AREA (1-1/2" from walls in corners and in the center of the test area)	±0.75°C/100°C Difference Measured From Ambient
THERMAL IMPEDANCE OF CHAMBER	Approximately 0.75°C/Watt
NULL DETECTOR CONTACT CLOSURE	Temperature Will Be Within 2°C Of Final Temperature At 3 Minutes After Closure Occurs
NULL DETECTOR CONTACT RATING	1 Amp, 240 VAC, With Contact Protection Provided By User To Protect Against Inductive Loads

NOTE: IT IS RECOMMENDED THAT THIS MANUAL BE READ THOROUGHLY BEFORE CONNECTING EQUIPMENT TO ELECTRICAL POWER SOURCE.

INTRODUCTION

This Delta Design, Inc. Chamber is a precision environmental test chamber capable of attaining temperatures from -73°C to +315°C with a minimal temperature deviation of ±0.1°C.

Temperature control in this chamber is by means of Delta's Solid State Controller, which can be operated manually or thru an external programmer.

CONTENTS

	PAGE
SPECIFICATIONS	i
INTRODUCTION	iii
ILLUSTRATIONS	v
1 PRECAUTIONS	1
2 OPERATING INSTRUCTIONS	4
2.1 Uncrating	4
2.2 Power Connection	4
2.3 Liquid Coolant	4
2.4 Liquid Nitrogen	5
2.5 Adjusting the Failsafe	6
2.6 Reading the Temperature Setting of the Dial Indicator	6
2.7 Programming	7
3 CHAMBER & CONTROLLER DESCRIPTION	8
3.1 Chamber	8
3.2 Solid State Controller	8
3.3 Null Detector Circuit	9
4 WARRANTY	10

ILLUSTRATIONS

	PAGE
FIGURE 1 - OPERATING INSTRUCTIONS	3
FIGURE 2 - TEMPERATURE SET DIAL	7
TROUBLE SHOOTING CHART	11
FIGURE 3 - CHAMBER AIR FLOW PATTERN	12
FIGURE 4 - COMPONENT IDENTIFICATION	13
FIGURE 5 - COMPONENT REMOVAL	14
FIGURE 6 - TEMPERATURE CONTROL SYSTEM	15
SCHEMATIC DIAGRAM 120V CO_2 W/LN_2 & DUAL OPTIONS	
SCHEMATIC DAIGRAM 240V W/LN_2 & DUAL OPTIONS	
CHAMBER, TYPE V CONTROLLER RETROFIT - 3900	

1 PRECAUTIONS

1.1 Connect SAFETY PLUG (rear of chamber) when external programmer is not being used. This will preclude any accidental high temperature being obtained if the MODE switch is placed in the PROGRAM position with no programmer connected.

1.2 Ground the case of the chamber to earth ground. When a grounded outlet is not available, use the three-to-two adaptor and connect the green colored "pigtail" to earth ground. The chamber must not be operated without the case grounded.

1.3 Unplug the chamber from all sources of power before attempting any type of servicing or removal of the controller chassis. The case of the triac switch assembly, located on the controller subassembly, is at power line potential and extreme care in servicing or calibration must be exercised.

1.4 Do not block the sides of chamber or outlet of controller area on bottom of the chamber for cooling purposes.

1.5 Ensure that the correct type of LCO_2 (liquid carbon dioxide) source is connected to the chamber before operating at low temperature. Recommend standard 50 pound capacity high dry siphon LCO_2 supply. Test the LCO_2 for cleanliness by discharging a quantity of it through a clean white handkerchief. Bits of rust and traces of oil, ice or water indicate contaminated LCO_2 which should not be used.

1.6 Operate the chamber at a temperature of 200°C for an hour after prolonged operation at low temperatures. This restores the efficiency of the insulating material by driving out the moisture which has been condensed out of the air.

CAUTION

Liquid oxygen may be formed in the insulation when the chamber is operated at low temperatures. Any mixture of oil and liquid oxygen can be explosive. If oil contamination is suspected, bake the chamber out by operating it at a temperature of 200°C for a period of three hours before taking it to extremely low temperatures.

1.7 Do not leave liquid nitrogen trapped in a line (valves closed at both ends) as high pressures will be developed as the liquid absorbs heat and becomes gas.

FAILSAFE ADJUST- LOCATED ON FRONT OF CHAMBER
TURN TO CHANGE TEMPERATURE AT WHICH FAILSAFE WILL TRIP
CAUTION: DO NOT LOWER FAILSAFE TEMP. SETTING UNLESS HEAT SW. IS ON & FAILSAFE IS OFF.

FAILSAFE LAMP- GLOWS RED WHEN FAILSAFE IS TRIPPED



THERMOMETER- INDICATES CHAMBER TEMP. IN TEST VOLUME.

(5) HEAT SWITCH & LIGHT-- SWITCH ON--ON POSITION ALLOWS CONTROLLER TO APPLY HEAT AUTOMATICALLY TO MAINTAIN SELECTED TEMPERATURE IN CHAMBER RED LIGHT IS ON STEADY WHEN CHAMBER IS HEATING, BLINKS WHEN CHAMBER REACHES SELECTED TEMPERATURE ABOVE AMBIENT

(4) COOL SWITCH & LIGHT--SWITCH ON--ON POSITION ALLOWS CONTROLLER TO APPLY COOLANT AUTOMATICALLY TO MAINTAIN SELECTED TEMPERATURE IN CHAMBER GREEN LIGHT IS ON STEADY WHEN CHAMBER IS COOLING.

(3) POWER SWITCH & LIGHT--SWITCH ON MAIN POWER ON WHITE LIGHT GLOWS WHEN POWER IS ON.

(2) TEMPERATURE SET DIAL--SET TO DESIRED TEMPERATURE. SELECTS CHAMBER TEMPERATURE IF MODE SWITCH IS IN MANUAL POSITION.

(1) MODE SWITCH--SET TO MANUAL POSITION. ASSIGNS THE SELECTION OF CHAMBER TEMPERATURE TO TEMPERATURE SET DIAL OR EXTERNAL PROGRAMMER.

MANUAL POSITION: TEMPERATURE SET DIAL DETERMINES CHAMBER TEMPERATURE.

PROGRAM POSITION: PROGRAMMING RESISTANCE CONNECTED TO PROGRAM JACK AT REAR OF UNIT SELECTS CHAMBER TEMPERATURE.

CAUTION: ALWAYS CONNECT SAFETY PLUG (AT REAR OF CHAMBER) WHEN AN EXTERNAL PROGRAMMER IS NOT BEING USED

OPERATING INSTRUCTIONS:

A. INSTALL THE CHAMBER. CONNECT POWER CORD TO SUITABLE OUTLET & COOLANT SUPPLY TO VALVE INLET.

B. FOLLOW STEPS 1 THRU 5.

Fig. 1

OPERATING INSTRUCTIONS
FIGURE 1

2 OPERATING INSTRUCTIONS

2.1 Uncrating - Remove all shipping tie downs and protective packaging.

2.2 Power Connection - Power connection should be an AC power source rated at 120V, 50/60 Hz single phase, 1875 Watts or 240V, 50/60 Hz single phase, 1875 Watts (240V option). The chamber must be connected to earth ground (green wire).

2.2.1 Delta chambers that operate on 240 VAC split the incoming phases for the coolant valve solenoid, failsafe relays, blowers and for the controller. The heater circuit operates on 240 VAC.

2.3 Liquid Coolant - Liquid Carbon Dioxide (LCO_2) - 1050 psi system (standard). Optional systems are LCO_2 - 300 psi, and Liquid Nitrogen (LN_2) - 100 psi.

2.3.1 Liquid Carbon Dioxide - 1050 psi system. A siphon type liquid CO_2 bottle is recommended.

2.3.1.1 Test the bottle by releasing a small amount of LCO_2 into a white handkerchief. Any brown stain indicates rust which would clog the filter and valve in the chamber. A wet handkerchief indicates water which would either freeze in the valve or clog the injector nozzle. Crack the LCO_2 valve open on the cylinder and notice the spray. It should be a dense, white cloud. It looks thin and gray when the tank is almost empty. An almost empty tank will not give proper cooling and should not be used. Connect the tank of LCO_2 to the rear of the chamber with the supplied high-pressure hose and fittings. Place a small amount of sealing compound on the threads of the male fitting to prevent leakage. DO NOT LET ANY SEALING COMPOUND GET INTO THE VALVE INLET ON THE REAR OF THE CHAMBER. Open the bottle and check for leaks which show as frosty spots on the hose or fittings.

2.3.2 Liquid Carbon Dioxide - 300 psi Low Pressure system.

2.3.2.1 When the in-plant use of liquid CO_2 exceeds approximately 1000 to 2000 pounds per month, a bulk liquid storage system can be

installed to reduce the cost of coolant. Chambers being operated with this type of system have to be fitted with a different CO_2 valve and injector than used on a 1050 psi system. Contact Delta for information concerning valve replacement. If new chambers are ordered for use with a bulk storage 300 psi system, the fact should be stated on the order.

> NOTE: The bulk storage system should be of the recirculating type if possible. If not, the supply should be located as close as possible to the chamber to minimize gas formation in the supply line. This is particularly important in low volume usage systems as the insulation and fluid flow are the factors that prevent boiling of CO_2 in the supply line. Gaseous CO_2 is not an effective coolant.

2.3.2.2 All lines, valves and connecting hoses should be blown out before the chamber is connected. Water is very troublesome and is apparently inherent in some low-pressure refrigerated supplies. If lines are opened to bleed off excessive pressure at shutdown, close them to prevent contamination by condensed moisture. This will help to keep ice from forming in the control valve.

2.4 Liquid Nitrogen

CAUTION

Oxygen in the air surrounding the chamber inner liner and in the insulation can be liquified at low temperatures. This creates an oxygen rich atmosphere surrounding the heater area. The chamber tends to be self purging as the nitrogen replaces the usual atmosphere near the heaters. Any mixture of oil and liquid oxygen can be explosive so extreme care must be used during operation at very low temperatures.

2.4.1 A 100 psi valve and stainless steel, polyurethane foam insulated, injector assembly is used for the liquid nitrogen applications. LCO_2 from a tank will not operate properly in a chamber equipped for LN_2.

2.4.2 Connect a liquid nitrogen liquid withdrawal container to the LN_2 input of the chamber with an insulated transfer line. A relief valve should be installed in the line with a relief pressure between 60 and 100 psi for a 2700 cubic foot 50 psi liquid withdrawal container.

2.5 Adjusting the Failsafe

2.5.1 To adjust the FAILSAFE high temperature protection unit, rotate the slotted FAILSAFE control. The trip temperature is increased by rotating the control counterclockwise and is lowered by turning the control clockwise. The FAILSAFE setting is preset at the factory at +315°C (maximum rating of standard chamber). If it is desirable to change the setting to a lower temperature setting, operate the chamber at the maximum temperature desired. Adjust the FAILSAFE until it is on the verge of tripping.

CAUTION

Do not rotate the FAILSAFE setting more than one full turn lower than the trip point, as this can damage the unit.

2.6 Reading the Temperature Setting of the Dial Indicator - See Figure 2.

2.6.1 Refer to example A - Set both dials at zero.

2.6.2 One complete rotation of the knob equals 100. Clockwise is plus (+) degrees(F or C) and counter-clockwise is minus (-) degrees. Each rotation of the knob is indicated by the small dial nearest the knob.

2.6.3 The large dial indicates each degree, every tenth numbered. Thus, as in example B, the large dial is set at 15, the small dial is beyond 3, therefore the setting is +315.

2.6.4 When setting to a minus (-) temperature it is necessary to subtract the degrees from 100, i.e., 20 from 100 equals "80" reading on the large dial to have a setting of -20. This is shown in example C.

It will be noted that the zero on the small dial is just to the left of the marker. Also, on the models having a range greater than -100, it is necessary to keep track of the counterclockwise rotation of the knob.



A
(0°)

B
(+315°)

C
(-20°)

FIGURE 2
TEMPERATURE SET DIAL

2.7 Programming

2.7.1 Connect the correct resistances between pins 1 and 3 of the PROGRAM Jack. Set the MODE Switch to PROGRAM and the HEAT and COOL switches to their ON positions. The controller will apply heat or coolant as needed to obtain the programmed temperature.

2.7.2 A Safety plug is provided with the chamber and should be kept connected to the PROGRAM input whenever an actual programmer or actual resistance is not connected. The safety plug will prevent the chamber from accidently being programmed to a very high temperature if the MODE Switch is placed in the PROGRAM position with an open PROGRAM input.

2.7.3 The safety plug disables the heat and cool circuits of the controller when the MODE Switch is placed in the PROGRAM position.

3 CHAMBER & CONTROLLER DESCRIPTION

3.1 Chamber

3.1.1 The chamber is a precision environmental test unit having a stainless steel interior, aluminum outer case and fiberglas insulation. The air circulation is closed and provided by 140 CFM blowers (see Figure 3).

3.1.2 The chamber is heated by applying full wave power to bobbin wound nichrome heating elements via the heat switch.

3.1.3 The chamber is cooled by injecting liquid CO_2 (liquid nitrogen in the LN_2 models) into the air stream through an expansion nozzle. The coolant flow is metered by a solenoid valve, controlled by the COOL solid state switch.

3.1.4 The temperature control system is shown in block diagram form as Figure 8 .

3.2 Solid State Controller

3.2.1 The controller compares the resistance of the temperature probe to the resistance of the indicated set point on the TEMPERATURE SET dial potentiometer or the digital resistance selection of the optional Digitemp controller. The resistance of a remote programming resistor is compared to the probe resistance of the MODE switch in the PROGRAM position.

3.2.2 The resistance of the probe will be either less than, equal to, or greater than the resistance of the TEMPERATURE SET potentiometer (or the DIGITEMP) , i.e., program resistance. These three situations directly correspond to the chamber temperature being lower than, equal to, or higher than desired. The controller applies heat, coolant, or withholds both to obtain and maintain the selected temperature in the chamber.

3.2.3 Mode - The controller is a three mode unit, i.e.:

(a) Heat only
(b) No heat or coolant
(c) Coolant only

This mode of control ensures that LCO_2 or LN_2 is not wasted in a continuous cycling of the heaters and coolant valve such as would be the case for a simple two mode output controller.

3.2.4 Further information on the controller may be found in the complete Type III Controller Manual included as part of this information package.

3.3 Null Detector Circuit

3.3.1 A contact closure is provided at the rear which functions when the chamber reaches the indicated set point of the controller. This contact closure may be used to signal external equipment that the chamber has reached selected temperature.

3.3.2 The Delta Design Model 9308 HI-LO Step Programmer, Model 9311 TEN STEP Programmer, and the Model 9313 HI-LO AMBIENT Programmer utilize the null contacts to start their timers when they are used with the chamber. This contact closure feature is most useful in automatic test programming applications.

4 WARRANTY

Delta Design, Inc. guarantees all products manufactured and sold by it to conform to published specifications and against defective material and workmanship for a period of 90 days from the date of our shipment. Temperature chambers and electronics are warranted for one year from date of shipment. All contactor assemblies are warranted for a period of 90 days or 1/2 million cycles. Obligation under these warranties is limited to repair or replacement by Delta at its plant or one of its authorized service stations, on any of our products which Delta determines to be defective or not in accord with stated specifications. Delta will not accept responsibility for any defect caused by improper use, nor will Delta assume liability for any unauthorized repairs or modifications to its products or materials, even though defective or not in accord with the specifications. In no case will responsibility extend to products, materials, or equipment not manufactured by Delta. All products to be returned to Delta's plant for warranty repair must have prior written approval from Delta Design, Inc., and all return transportation charges will be at the buyer's expense. Delta will not accept liability for any unauthorized returns. No liability will be accepted for any damages to customer's materials, and equipment due to the use or misuse of Delta's products, nor for any loss of profits or other special damages. Delat Design, Inc., reserves the right to change price, design features and/or specifications without notice.

TROUBLE SHOOTING: ELECTRICAL

HOW TO USE THIS CHART

1. Turn Mode Switch to Manual.
2. Note Thermometer Reading (Chamber Temperature)
3. Turn Heat and Cool Switches On.
4. Turn Temperature Set Control 50° Higher than Chamber Temperature and note the conditions of the Heat and Cool Lamps.
5. Turn Temperature Set Control 50° Lower than Chamber Temperature and note the conditions of the Heat and Cool Lamps.

These two situations determine the correct block to read in the chart:

6. Enter the Chart at the Top for the conditions observed in step 4. (50° Higher than Chamber Temperature.)
7. Enter the Chart at the Left Side for the conditions observed in step 5. (50° Lower than Chamber Temperature.)

		LIGHT STATE WITH TEMPERATURE SET DIAL 50° HIGHER THAN CHAMBER TEMP.			
LIGHT STATE WITH TEMPERATURE SET DIAL 50° LOWER THAN CHAMBER TEMP.		RED - OFF GREEN - OFF	RED - ON GREEN - OFF	RED - OFF GREEN - ON	RED - ON GREEN - ON
	RED - OFF GREEN - OFF	Probe Element shorted to case. (Replace) Failure on Amplifier P.C. Board. (Trace signal with scope) Transformer Winding open.	Cool Circuit has failed. Trace signals with scope.		
	RED - ON GREEN - OFF		Probe shorted out. Temp. set Pot. — open. Cool Anticipator winding open. Check between Terminal A and Case of Q8 for 10Ω.		
	RED - OFF GREEN - ON	Failsafe Relay K1 not energizing. Coil resistance will be Approx. 10K. Failsafe open. Heat Triac failed.	NORMAL	Probe Open. Temp. Set. Pot. shorted. Heat Anticipator Winding open: Check between B and Case of Q9 for 10Ω.	Cool Circuit has failed — Trace signal with scope.
	RED - ON GREEN - ON		Heat circuit has failed — Trace signal with scope. Triac failed.		



SIDE VIEW

FIGURE 3

CHAMBER AIR FLOW PATTERN



FIGURE 4
COMPONENT IDENTIFICATION

TO REMOVE BLOWER MOTORS

1. Unplug chamber power cord.
2. Do not remove rear panel.
3. Remove 4 screws and lay grill aside.
4. Remove wire nuts connecting motor to chamber power.
5. Remove two screws that mount motor to chamber.
6. Pull motor straight back to remove.

TO REMOVE HEATER

1. Unplug chamber power cord.
2. Remove and lay rear panel horizontally behind chamber.
3. Unpack fiberglas to expose heaters.
4. Remove wires from each heater unit.
5. Remove mounting screws.
6. Pull out heater assembly.



TO REMOVE CO_2 VALVE

1. Unplug chamber power cord.
2. Remove screws from right side cover.
3. Place right side cover on top of chamber.
4. Unscrew wire nuts.
5. Remove screws and take out CO_2 valve.



TO REMOVE LN_2 PACKAGE

1. Unplug chamber power cord.
2. Remove screws holding cover on valve assembly.
3. Remove screws holding valve to standoffs.
4. Remove nut joining inlet tubing to valve.
5. Pull valve away from chamber rear panel and remove wire nuts.

FIGURE 5
COMPONENT REMOVAL

TO REMOVE BLOWER MOTORS

1. Unplug chamber power cord.
2. Do not remove rear panel.
3. Remove 4 screws and lay grill aside.
4. Remove wire nuts connecting motor to chamber power.
5. Remove two screws that mount motor to chamber.
6. Pull motor straight back to remove.

TO REMOVE HEATER

1. Unplug chamber power cord.
2. Remove and lay rear panel horizontally behind chamber.
3. Unpack fiberglas to expose heaters.
4. Remove wires from each heater unit.
5. Remove mounting screws.
6. Pull out heater assembly.



TO REMOVE CO_2 VALVE

1. Unplug chamber power cord.
2. Remove screws from right side cover.
3. Place right side cover on top of chamber.
4. Unscrew wire nuts.
5. Remove screws and take out CO_2 valve.



TO REMOVE LN_2 PACKAGE

1. Unplug chamber power cord.
2. Remove screws holding cover on valve assembly.
3. Remove screws holding valve to standoffs.
4. Remove nut joining inlet tubing to valve.
5. Pull valve away from chamber rear panel and remove wire nuts.

FIGURE 5
COMPONENT REMOVAL



TEMPERATURE CONTROL SYSTEM
SOLID STATE, TYPE III
DELTA DESIGN INC.

A = NULL DETECTOR SCHMITT
(REED RELAY OUTPUT)
PRODUCES CONTACT CLOSURE
FOR /P/ = /S/

B = HEAT. SCHMITT
(REED RELAY OUTPUT)
PRODUCES CONTACT CLOSURE
FOR /P/ INPUT AT AMPLIFIER
GREATER THAN /S/

C = COOL. SCHMITT
(REED RELAY OUTPUT)
PRODUCES CONTACT CLOSURE
FOR /S/ GREATER THAN /P/

FIGURE 6



REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPD
	A	PER ECN M1174 04-18 77 TRL	04 APR 77	
	B	PER ECN M 1953 10 DEC 79 BQP • ADDED SHT 2 & NOTES FOR TYPE V CONTROLLR.	18 DEC	

△6 USED ON CO_2 LN_2 DUAL MODEL ONLY

△5 E7 TO TB1-11 & E9 TO TB1-11 DISCONNECTED AND NOT USED ON CO_2 LN_2 DUAL MODEL ONLY

△4 E7 & E8 DISCONNECTED AND NOT USED ON LN_2 MODEL ONLY

△3 E9 & E10 DISCONNECTED AND NOT USED ON CO_2 MODEL ONLY

△2

△1 CAUTION—DO NOT REMOVE P2 UNLESS A PROGRAMMER IS TO BE INSTALLED

NOTES:

NOTE:
- THIS SHT SHOWS CHAMBER WIRING FOR USE WITH TYPE III CONTROLLER
- SEE SHT 2 FOR TYPE V.

HIGHEST REFERENCE DESIGNATION: A3 TB2 R1 W3 E12 S2 U3 L3 K1 / B2 J1 L2 P2 CB1
REFERENCE LETTER NOTATION

REF	0836542	6300				
REF	0263080	5300				
REF	0263283	5300	703904611 ON	8 & 12		

DASH QTY	NEXT ASSY	USED ON
APPLICATION		

SERIAL NO. | DATE EFF | DWG REV
EFFECTIVITY

JUNIOR DIMENSIONAL MACHINE DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS: .X ± .03; .XX ± .010; .XXX ± .005
ANGLES: 0° 30'
HOLE TOLERANCES

MATERIAL △
FINISH △

ENGINEERING ACTIVITY		
DESIGN		
DRAFTED	L. FUENTES 1/23/76	
CHECKED		1/23/76
APPROV		1/4/76
RELEASE		

DO NOT SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CONIC INC.
8750 KEARNY VILLA RD SAN DIEGO CA. 92126 TEL (714) 279-8880

TITLE: SCHEMATIC DIAGRAM, 120 V CO2 W/LN2 & DUAL OPTIONS

SIZE	CODE IDENT	
D		1643470 B
SCALE —		SHEET 1 OF 2



REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPD.
	A	PER ECN M1174 04-18-77 TRL	04-18-77	
	B	PER ECN M1953 10DEC79 BDP ADDED SHT 2 & NOTES FOR TYPE V CONTROLER.	1/4/80	

NOTE:
- THIS SHT SHOWS CHAMBER WIRING FOR USE WITH TYPE V CONTROLLER.
- SEE SHT 1 FOR TYPE III

NOTES:

1. THICK LINES INDICATE HEAT POWER CIRCUITRY
2. E7 TO TBI-11 & E9 TO TBI-11 DISCONNECTED AND NOT USED ON CO_2 LN_2 DUAL MODEL ONLY
3. E7 & E8 DISCONNECTED AND NOT USED ON LN_2 MODEL ONLY
4. E9 & E10 DISCONNECTED AND NOT USED ON CO_2 MODEL ONLY
5. USED ON CO_2 LN_2 DUAL MODEL ONLY

HIGHEST REFFRENCE DESIGNATIONS

A3	TB2	R1	W3	E12	S2	DS1	C3			K1
B2	J1		L2	P2	CB1					

REFFRENCE DESIGNATIONS NOT USED

REF	D2636342	6400								
REF	D2636601	5900								
REF	D2362283	5900	03890-46160	8-6-76						
BASE QTY	NEXT ASSY	USED ON	SERIAL NO.	DATE EFF	DWG REV	MATERIAL				
APPLICATION			EFFECTIVITY			FINISH				

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES TOLERANCES ON DECIMAL .XX ± .010 .XXX ± .005 ANGULAR ± 30' HOLE TOLERANCES .015 ± .005 .031 ± .005 .062 ± .005 .093 ± .005 .125 ± .005 .156 ± .005 .187 ± .005 .218 ± .005 .250 ± .005 .281 ± .005 .312 ± .005 .343 ± .005 .375 ± .005 .406 ± .005 .437 ± .005 .468 ± .005 .500 ± .005

ENGINEERING ACTIVITY		
DESIGN		
DRAFTED	L F UNTIEDT	1/23/76
CHECKED		
APPROV		4/6/76
RELEASE		
DO NOT SCALE DWG		

DELTA DESIGN INC.
A SUBSIDIARY OF CONIC INC.
11750 KEARNY VILLA RD SAN DIEGO, CA. 92123 TEL (714) 279-8000

TITLE: SCHEMATIC DIAGRAM, 120 V CO2 W/LN2 & DUAL OPTIONS

SIZE	CODE IDENT		
D		1643470	B
SCALE —		SHEET 2 OF 2	



REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPD
	A	PER ECN M 1460 BGM 5-25-78	5-25-78	
	B	PER ECN M 955 10 DEC 79 BGM ADDED SHT 2 & NOTE 4 FOR TYPE V CONT	12-20-79	

NOTES:

1. CAUTION – DO NOT REMOVE F2 UNLESS A PROGRAMMER IS TO BE INSTALLED
2.
3. E9 & E10 DISCONNECTED AND NOT USED ON CO_2 MODEL ONLY
4. E7 & E8 DISCONNECTED AND NOT USED ON LN_2 MODEL ONLY
5. E7 TO TB1-11 & E9 TO TB1-11 DISCONNECTED AND NOT USED ON CO_2 LN_2 DUAL MODEL ONLY
6. USED ON CO_2 LN_2 DUAL MODEL ONLY
7. USED ONLY ON 220V MODEL 3900 WITH UNIVERSAL TEST TRAY OVERRIDE SEE SHT 2.

NOTE:
- THIS SHT SHOWS CHAMBER WIRING. FOR USE WITH TYPE III CONTL
- SEE SHT 2 FOR TYPE V

HIGHEST REFERENCE DESIGNATIONS

A3	TB2	R1	N3	E12	S2	DS1	C3	TH	K1	
B2	J1		L2	P2	CB1					

REFERENCE DESIGNATIONS NOT USED

DASH QTY	NEXT ASSY	USED ON	SERIAL NO.	DATE EFF	DWG REV
APPLICATION			EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS: .XX ±.03, .XXX ±.010
ANGLES: 0° 30'
HOLE TOLERANCES

.062 to .124	+.004 −.000	+.005 −.000
.125 to .249	+.005 −.000	+.005 −.000
.250 to .499	+.006 −.000	+.005 −.000
.500 to .749	+.007 −.000	+.005 −.000

FINISH

ENGINEERING ACTIVITY: ECN M1152

DESIGN	
DRAFTED	
CHECKED	
APPROV	2/26/79
RELEASE	

DO NOT SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CONV INC.
3726 KEARNY VILLA RD SAN DIEGO, CA. 92123 - TEL (714) 292-5000

TITLE: SCHEMATIC DIAGRAM 240V OPTIONS W/LN2 & DUAL

SIZE	CODE IDENT		
D		1643471	B

SCALE —— SHEET 1 OF 2



NOTE: THIS SHT SHOWS CHAMBER WIRING FOR USE WITH TYPE V CONTROLLER. SEE SHT 1 FOR TYPE III

4 E7 & E8 DISCONNECTED & NOT USED, ON LN_2 MODEL ONLY.

3 E9 & E10 DISCONNECTED & NOT USED, ON CO_2 MODEL ONLY.

2. THICK LINES INDICATES HEAT POWER CIRCUIT.

1.

7 USED ONLY ON 220V MODEL 3500 WITH UNIVERSAL TEST TRAY OVERSEAS SHIPMENT

6 USED ON CO_2-LN_2 DUAL MODEL ONLY

5 E7 TO TB1-11 & E TO TB1-11 DISCONNECTED & NOT USED, ON CO_2-LN_2 DUAL MODEL ONLY.

NOTES: UNLESS OTHERWISE SPECIFIED

ENGINEERING ACTIVITY M1953

DESIGN

DRAFTED ONE JAN X 12/20/79

CHECKED

APPROV

RELEASE

DO NOT SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CENCO INC.
SAN DIEGO, CA. 92138

TITLE: SCHEMATIC DIAGRAM 240V W/LN_2 & DUAL OPTIONS

SIZE D CODE IDENT

1643471

SCALE

SHEET 2 OF 2

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPROVED
	A	PER ECN M1401 5-7-78 BGM REVISED NOTE 3	5-7-78	







1.) MOTOR: 115 V. 50/60 Hz (NOTHERMAL PROTECTION) SEALED BALL BEARING SHAFT ROTATION

2.) IMPELLER: REVCOR #9381-187S (CCW ROTATION) ALTER PER B1G32186

3.) RTV ITEM 7 TO ITEM 6; ATTACH ITEM 3 (MOTOR PLATE) TO ITEM 1 (MOTOR) USING HARDWARE, THEN RTV TO ITEM 6

4.) BLOWER MOTOR ASSY RATED AT 140 C.F.M. AIR MOVEMENT, NOM.

⚠3 TAPE ITEMS 4 & 10 IN PLACE TO PREVENT BEING JARRED LOOSE BEFORE INSTALLING ON CHAMBER.

QTY. REQ'D	NOMENCLATURE OR DESCRIPTION	CODE IDENT	IDENTIFYING NUMBER	SPECIFICATION	MATERIAL OR NOTE	ITEM NO.

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES
TOLERANCES ON
FRACTIONS ± 1/64 | DECIMALS .XX ± .010, .XXX ± .005 | ANGLES ± 1/2°

MATERIAL:

FINISH:

	BY	DATE
DESIGN	L.ELLIS	5/7/78
DRAFTED	L.ELLIS	5/7/78
CHECKED	Hamm	5-8-78
APPROV		

DELTA DESIGN INC.
9000 FLETCHER PKWY
LA MESA, CALIF. 92041
TEL. A/C 714, 465-4141

TITLE: 50/60 Hz BLOWER MTR. ASSEMBLY CW SHAFT ROTATION

MODEL NO. STD PART
PART NO. 2621006

SIZE D | CODE IDENT NO. | DRAWING NO. 2621006 | REV. LTR. A

SCALE FULL | SHEET 1 OF 1

MULTI-USAGE STD | 8-5-70 | WIC
NEXT ASSY | USED ON | SERIAL NOS. | DATE EFF. | DWG. REV. LTR.
APPLICATION | EFFECTIVITY

NOTES:

BLUE CARD

REVISIONS			
ZONE	LTR	DESCRIPTION	DATE
	A	PER ECN 1401 BGM 4-17-78 REVISED NOTE 5	5-4-78





1) MOTOR: 115 V. 50/60 Hz (NO THERMAL PROTECTION) SEALED BALL BEARING SHAFT ROTATION

2) IMPELLER: REVCOR #9381-1875 (CW. ROTATION) ALTER PER B1632185

3) RTV ITEM 7 TO ITEM 6, ATTACH ITEM 3 (MOTOR PLATE) TO ITEM 1 (MOTOR) USING HARDWARE, THEN RTV TO ITEM 6

4) BLOWER MOTOR ASSY. RATED AT 140 C.F.M. AIR MOVEMENT, NOM.

5) TAPE ITEMS 4 & 10 IN PLACE TO PREVENT BEING JARRED LOOSE BEFORE INSTALLING ON CHAMBER.

NOTES:

QTY. REQ'D	NOMENCLATURE OR DESCRIPTION	CODE IDENT	IDENTIFYING NUMBER	SPECIFICATION	MATERIAL OR TYPE
1	50/60 Hz BLOWER MTH ASSEMBLY CCW SHAFT ROTATION		2621007		

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES
TOLERANCES ON FRACTIONS ± 1/64, DECIMALS .01 ± .010, .XXX ± .005, ANGLES ± 1/2°

	BY	DATE
DESIGN	L. ELLIS	
DRAFTED	L. ELLIS	
CHECKED		
APPROV.		

MATERIAL:

FINISH:

DELTA DESIGN INC. 9500 FLETCHER AVE. LA MESA, CALIF. 92041 TEL. (714) 465-4140

MODEL NO. STD PART

PART NO. 2621007

SIZE D | CAGE CODE NO. | DRAWING NO. 2621007 | REV. A

SCALE | WEIGHT | SHEET 1 OF 1

MULTI-USAGE	STD		8-3-78 N/C
NEXT ASSY	USED ON	SERIAL NOS.	DATE OF DWG. REV. LTR.
APPLICATION		EFFECTIVITY	

1135F67

REVISIONS				
ZONE	LTR.	DESCRIPTION	DATE	APPROVED
	A	PER ECN M 1897 J.RAMER 10-15-72 REMOVED ITEM #5. (WAS ASBESTOS INSTEAD OF CORK GASKET)	10-16-9	





SECT. A-A

DASH	HTR RES
-001	8.75 Ω
-002	15.0 Ω
-003	17.5 Ω
-004	20.0 Ω

P/L "B" SIZE

QTY. REQ'D	NOMENCLATURE OR DESCRIPTION	CODE IDENT.	IDENTIFYING NUMBER	SPECIFICATION	MATERIAL OR NOTE	ITEM NO

1. ALL DIM. ARE REF ONLY.

NOTES:

UNLESS OTHERWISE SPECIFIED THE FOLLOWING APPLIES
BREAK ALL SHARP EDGES .005
MAX. SURFACE ROUGHNESS 125 RMS
THDS: INT CL 2B, EXT. CL 2A

MULTIPLE STD USAGE

NEXT ASSY	USED ON	SERIAL NOS	DATE EFF	DWG REV. LTR
APPLICATION		EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES
TOLERANCES ON
FRACTIONS ± 64 ANGLES ± ½°
DECIMALS .XX ± .010
.XXX ± .005

MATERIAL:

FINISH

DO NOT SCALE DRAWING

PART NO NOTED

	BY	DATE
DESIGN		
DRAFTED	K NAPP	5-1-72
CHECKED	Harris	7-6-72
APPROV.	L. [illegible]	7-6-72

DELTA DESIGN INC.
8000 FLETCHER PKWY.
LA MESA, CALIF 92041
TEL: A/C (714) 465-4141

TITLE: HEATER ASSY

SIZE	CODE IDENT NO	DRAWING NO	REV LTR
B		26225 24	

SCALE FULL SHEET 1 OF 1

BLUE CARD

REVISIONS				
ZONE	LTR	DESRIPTION	DATE	APPD
	A	PER ECN 1365 BGM 3-30-78 ITEM 4 WAS ITEM 1, ITEM 4 REDRAWN FOR ACCURACY	4-14-78	
	B	PER ECN M1521 BGM 7-21-78 ITEM 2 UPDATED, A, B, + C DIMS IN TABULATION BLOCK CHANGED, SEE ECN	7-31-78	



DASH NO	A	B	C	USED ON
-001	16.75	22.25	14.25	3900 B
-002	17.00	24.25	16.25	3900 R
-003	16.25	25.75	17.75	6400
-004				8000
-005				8000
-006	17.25	17.25	13.25	4100
-007				
-008				
-009				
-010				

DASH NO	A	B	C	USED ON
-011				
-012				
-013				
-014				
-015				
-016				
-017				
-018				
-019				
-020				

⚠ FINISH (IF APPLICABLE)

⚠ MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

DASH	QTY	NEXT ASSY	USED ON	SERIAL NO.	DATE EFF	DWG REV
		MULTIPLE		STD USAGE		
APPLICATION				EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS .XX ± .03 .XXX ± .010
ANGLES 0° 30'

HOLE TOLERANCES

.013 THRU .123	+ .004 - .001	.251 THRU .500	+ .006 - .001
.126 THRU .250	+ .005 - .001	.501 THRU .750	+ .008 - .001

MATERIAL ⚠
FINISH ⚠

ENGINEERING ACTIVITY

DESIGN	
DRAFTED	KNAPP 3-30-73
CHECKED	MATTHEW 4-6-73
APPROV	Harris 4-6-73
RELEASE	

DO NOT SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CONU INC.
8725 KEARNY VILLA RD SAN DIEGO, CA. 92123 - TEL (714) 292-5000

TITLE: CO_2 ASSY (900 PSI) DUAL STEM

SIZE	CODE IDENT	
B		2618018

SCALE 1/2 X SHEET 1 OF 1

REVISIONS				
ZONE	LTR	DESRIPTION	DATE	APPD
	A	PER ECN 1365 BGM 3-30-78 VALVE ASSY (ITEM 4) REDRAWN, ITEM 4 WAS 1	4-14-78	
	B	PER ECN M1521 BGM 7-21-78 ITEM 2 UPDATED. A, B, & C DIMS IN TABULATION BLOCK CHANGED, SEE ECN	7-31-78	



DASH NO	A	B	C	USED ON
-001	16.75	22.25	14.25	3900 B
-002	17.00	24.25	16.25	3900 R
-003	16.25	25.75	17.75	6400
-004				8000
-005				8000
-006	17.25	17.25	13.25	4100
-007				
-008				
-009				
-010				

DASH NO	A	B	C	USED ON
-011				
-012				
-013				
-014				
-015				
-016				
-017				
-018				
-019				
-020				

⚠ FINISH (IF APPLICABLE)

⚠ MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

DASH	QTY	NEXT ASSY	USED ON
		MULTIPLE	
APPLICATION			

SERIAL NO.	DATE EFF	DWG REV
TO USAGE		
EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMAL: XX ± .03, .XXX ± .010
ANGLES 0°30'
HOLE TOLERANCES

MATERIAL ⚠
FINISH ⚠

ENGINEERING ACTIVITY

DESIGN	
DRAFTED	KNAPP 4-7-78
CHECKED	[illegible] 4-6-78
APPROV	Hanna 4-6-78
RELEASE	

DO NOT SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CONTROL INC.
3729 KEARNY VILLA RD SAN DIEGO, CA 92123 • TEL 714 292-9000

TITLE: CO_2 ASSY (300 PSI) DUAL STEM

SIZE	CODE IDENT	
B		2618017

SCALE 1/2 X

SHEET 1 OF 1

BLUE CARD

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPD



DASH	PSI	PN
-001	900	1800117
-002	300	1800105

⚠ FINISH (IF APPLICABLE)

⚠ MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

DASH	QTY	NEXT ASSY	USED ON
		MULTI-USAGE	
APPLICATION			

SERIAL NO.	DATE EFF	DWG REV
EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS
.XX ± .03
.XXX ± .010
ANGLES
0° 30'

HOLE TOLERANCES

.013 THRU .125	+.004 −.001
.126 THRU .375	+.006 −.001
.376 THRU .500	+.008 −.001
.501 THRU .750	+.008 −.001
.751 THRU .500	+.004 −.001

MATERIAL ⚠
FINISH ⚠

ENGINEERING ACTIVITY	
DESIGN	
DRAFTED	BGM 3-24-78
CHECKED	
APPROV	
RELEASE	

DO NO SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CONU INC.
SAN DIEGO, CA. 92123

TITLE: CO_2 VALVE + BRACKET ASSY

SIZE	CODE IDENT	
B		1647407

SCALE 1/1 SHEET 1 OF 1

REVISIONS				
ZONE	LTR	DESCRIPTION	ATE	APPD



DASH	QTY	NEXT ASSY	USED ON	SERIAL NO.	DATE EFF	DWG REV
C01	1	1640111	8000			
001	1		7650			
001	1	2636342	6400			
001	1	2635601	5700			
001	1	2636283	3900			
001	1	2635402	2850			
C01	1	2605110	2300			
APPLICATION				EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS: .XX ± .03, .XXX ± .010
ANGLES: 0° 30'

HOLE TOLERANCES

.013 THRU .128	+ .004 − .001	.251 THRU .500	+ .006 − .001
.136 THRU .250	+ .005 − .001	.501 THRU .750	+ .005 − .001

MATERIAL ⚠1
FINISH ⚠2

ENGINEERING ACTIVITY	
ECN M1622	
DESIGN	B NIELSEN 10-2-8
DRAFTED	
CHECKED	
APPROV	
RELEASE	
DO NOT SCALE DWG	

DELTA DESIGN INC.
A SUBSIDIARY OF CONIU INC.
SAN DIEGO, CA. 92123

TITLE: HOSE SHIP KIT

SIZE	CODE IDENT	
C		2618020
SCALE 1/1		SHEET __ OF __

⚠ FINISH (IF APPLICABLE)

⚠ MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

BLUE CARD

INDEX OF ASSEMBLIES - MODEL 3900 CHAMBER

	TITLE	SIZE & NO.	SHEET
1.	Innerliner Assembly	D2636288	1
2.	Innerliner Spotweld Assembly	D2636289	1
3.	Door Jamb Assembly	D2603156	1
4.	Sheet, Plenum Assembly	D2600223	1
5.	Top Sheet Assembly	D2636291	2
6.	Left Sheet Assembly	D2600112	2
7.	Right Sheet Assembly	D2600111	2
8.	Baffle Assembly	C2600225	3
9.	Scroll	D2635606	3
10.	Can Assembly	B2632196	3
11.	Rear Panel Assembly	D2630571	4
12.	Bottom Panel Assembly	D2600116	4
13.	Right Panel Assembly	D2636287	4
14.	Partition Panel Assembly	D2636290	5
15.	Bezel Assembly	C2600100	5
16.	Weld Assembly - Tube Guide	B1640309-001	5
17.	Thermoswitch Assembly (S1)	B2602503	6
18.	Blower Motor Assembly (B1)	D2621006	6
19.	Blower Motor Assembly (B2)	D2621007	7
20.	Heater Assembly (HR1, HR2)	B2622524-001	7
21.	Heater Element Assembly	B2635875-001	7
22.	CO_2 Assembly, Dual Stem (L1)	B2618018-001	8
23.	CO_2 Injector Assembly	B1647844-002	8
24.	CO_2 Valve & Bracket Assembly	B1647407-001	8
25.	Cable Assembly (W1)	A2635264-005	9
26.	Cable Assembly (W2)	A2635265-005	9
27.	Cable Assembly (125V) (W3)	A2635833-003	9

	TITLE	SIZE & NO.	SHEET
28.	LN_2 Injector Assembly	C2619064-001	9
29.	Hose Ship Kit	C2618020-001	11
30.	Capacitor Mod. (C2, C3)	A2635048	11
31.	CO_2 Assy, Dual Stem (300 PSI)	B2618017-001	12
32.	Injector Assy, CO_2 Dual Stem	B1647844-001	12
33.	CO_2 Valve & Bracket Assy	B1647407-002	12
34.	Plug Mod.	B2600409-001	12
35.	Interconn. Assy - Type V Controlr with IEEE-488	D1650223	Multi-Usage
36.	Chamber Type V Controlr Retrofit 3900	D1650240	13

P/L 2636283 REV ____ SHT 1 OF 13

DESCRIPTION TOP ASS'Y 3900 CHAMBER

NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP
D	1521	[illegible]	[illegible]	[illegible]
E	[illegible]	10-4-78	[illegible]	[illegible]
F	[illegible]	11-7-78	[illegible]	[illegible]
G	1719	12-5-78	[illegible]	[illegible]

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING PO NO	QTY DUE	REC'D	MANUFACTURE ACT STD HRS	EST ACT COM	ACT COM	PLATE/PAINT IN	OUT	APP'D
00	X					D	2636283	K	CHAMBER ASS'Y., 3900		2636283													
00	REF					D	1643470	A	SCHEMATIC DIAGRAM 120V															
00	REF					D	1643471		SCHEMATIC DIAGRAM 240V															
~~00~~	~~REF~~					~~C~~	~~1635836~~		~~120 VAC TO 240 VAC CONVERSION~~		~~2635836~~													
00	REF					D	1643453	B	CO_2 & LN_2 CHAMBER CONVERSION ASS'Y.		1643453-001													
00	REF					D	2639167	C	CO_2 & LN_2 DUAL CONVERSION		2639167													
~~00~~	~~REF~~					~~C~~	~~1640222~~	A	~~LN_2 INSTAL. ASS'Y, VALCOR VALVE (IN FIELD)~~		~~1640222-007~~													
00	REF					P/L	1648289		TOP ASSY, TYPE III CONTROLLER															
00	REF					D	1648384		ARTICULATED HINGE		1648384-001													
00	REF					P/L	1649919		VDE REQUIREMENTS		1649919-001													
00	REF					D	1650223		INTERCONNECT ASSY TYPE II CONTROLLER		MULTI-USAGE													
00																								
00																								
01	1					D	2636288	B	INNERLINER ASSY		2636288													
01	1					D	2636289	A	INNERLINER SPOTWELD ASS'Y		2636289													
00																								
00																								
01	1					D	2603156	C	JAMB ASS'Y., DOOR		2603156													
00																								
01	2					C	1600402	C	SHEET, JAMB LEFT & RIGHT		1600402													
02	2					C	1600403	C	SHEET, JAMB TOP & BOTTOM		1600403													
03																								
04																								
02	1					D	2600223	B	SHEET, PLENUM ASS'Y		2600223													
00																								
00																								
01	1					D	1600110	C	SHEET, BOTTOM INNERLINER		1600110													
02	2					C	1600106	B	SHEET, DEFLECTOR, RIGHT		1600106-002													
03	2					C	1600106	B	SHEET, DEFLECTOR, LEFT		1600106-001													
04	3					B	1602965	B	SPACER, SWAGED	1602965-001	4100085													
05	1					B	1634780	E	TUBE, SPACER		1634780-002													
06	1					B	1636321	A	TUBE, GUIDE		1636321-002													
07	1					B	1634780	E	TUBE, GUIDE		1634780-003													

NOTES: ⚠ THESE DWGS. ARE FOR OPTIONAL EQUIPMENT AND ARE NOT PART OF BASIC CHAMBER.

P/L 2636283

PL 2636283 REV ____ SHT 2 OF 13

DESCRIPTION TOP ASS'Y 3900 CHAMBER

NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP
U	M1947	5-23	RAP	

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O. NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.
08	1					C	1600114		SHEET, PLENUM INNERLINER		1600114-001
09											
10											
11											
12											
03	1					D	2636291	B	SHEET, TOP ASS'Y.		2636291
00											
00											
01	1					D	2636291	B	SHEET, TOP .032 THK SST COND. "A" FIN. 2B	SHT. TYPE 302-304	1636291-001
02	1					A	1600029	D	SHEET, TOP SUPPORT		1600029-003
03	2					B	1602965	B	STANDOFF, SWAGE	1602965-002	4100095
04	4								* 8-32 WELDNUT		1500185
05											
06											
04	1					D	2600112	E	SHEET, LEFT ASS'Y.		2600112
00											
00											
01	1					D	2600112	E	SHEET, LEFT .032 THK. SST COND. "A" FIN. 2B	SHT. TYPE 302-304	1600112-001
02	1					B	1634771	C	TUBE, CO_2 VENT		1634771-004
03	1					B	1630007	C	RETAINER, VENT TUBE		1630007
04											
05											
05	1					D	2600111	D	SHEET, RIGHT ASS'Y.		2600111
00											
00											
01	1					D	2600111	D	SHEET, RIGHT .032 THK SST COND. "A" FIN. 2B	SHT. TYPE 302-304	1600111-001
02	1					B	1640099		BRACKET, FAILSAFE		1640099
03											
04											
06	2					B	1634780	E	TUBE, GUIDE		1634780-004

PURCHASING: JOB QTY | AUL | QTY REC | FAB CD | P.O. NO | QTY DUE | REC

MANUFACTURE: ACT EST | ACT STD. HRS | ACT COM | COM

PLATE/PAINT: IN | OUT

AREA

NOTES:

P/L 2636283

PL 2636283 REV ____ SHT 3 OF 13
DESCRIPTION TOP ASS'Y 3900 CHAMBER
NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO	JOB QTY	ALL	QTY REC	FAB CD	PURCHASING PO NO	QTY	DUE	REC'D	MANUFACTURE ACT HRS	EST HRS	ACT COM	COM	PLATE/PAINT IN	OUT	AREA
07	1					B	1634774		TUBE, PROBE GUIDE		1634774-002															
08																										
09																										
10																										
02	1					C	2600225	C	BAFFLE ASS'Y.		2600225															
00																										
00																										
01	1					C	2600225	C	SHEET, BAFFLE UPPER	SHT. TYPE 302-304	1600225-001															
									.032 THK. SST COND. "A" FIN. 2B																	
02	1					C	2600225	C	SHEET, BAFFLE REAR	SHT. TYPE 302-304	1600225-002															
									.032 THK. SST COND. "A" FIN. 2B																	
03	1					C	2600225	C	SHEET, DEFLECTOR	SHT. TYPE 302-304	1600225-003															
									.032 THK. SST COND "A" FIN. 2B																	
04																										
05																										
06																										
03	2					D	2635606		SCROLL	2635606	2100701															
									(HOUSING ASS'Y., BLOWER WHEEL)																	
00																										
00																										
01	1								HOUSING, BLOWER WHEEL		2100701															
02	4								WELDNUT	CHIC NUT XW1713	1500189															
03																										
04																										
04																										
05	2					B	2632196	D	CAN ASS'Y	MULTI-USAGE	2632196-002															
00																										
00																										
~~01~~	~~1~~					~~B~~	~~1632350~~	~~C~~	~~CAN~~		~~1632350-002~~															
02																										
03																										
~~04~~	~~2~~					~~A~~	~~1631838~~	~~A~~	~~TAB~~		~~1631838~~															

NOTES:

P/L 2636283

P.L. 2636283 REV ____ SHT 4 OF 13

DESCRIPTION TOP ASS'Y 3900 CHAMBER

NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____ ____ ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	ALL	QTY REC	FAB CD	PURCHASING P.O. NO	QTY	DUE	REC	MANUFACTURE ACT STD HRS	EST ACT COM	COM	PLATE/PAINT IN	OUT	AREA
05	1								~~GROMMET~~		~~1500026~~														
06																									
07																									
08																									
06	2					B	1600015		RING, SCROLL		1600015														
07	5								* 6-32 UNC × .38 PHP-MS		6806323-804														
08	4								* 6 × .38 PHP-SMS		6906380-400														
09	8								* 6 × .50 PHP-SMS		6906120-400														
10																									
11																									
12																									
13																									
14																									
15																									
02	1					D	1603080	H	PANEL, FRONT		1603080														
03	1					D	2630571	E	PANEL ASS'Y., REAR		2630571														
00																									
01	1					D	2630571	E	PANEL, REAR		1630571														
02	6								* 6-32 RIVNUT, CSK. HD.	A6-106	1700037														
03	2								* 6-32 PRESSNUT	S632-6	1700029														
04																									
05																									
04	1					D	1600118	G	TOP PANEL		1600118														
05	1					D	2600116	D	PANEL ASS'Y., BOTTOM		2600116														
00																									
01	1					D	2600116	D	PANEL, BOTTOM .062 AL ALY	SHT. 3003-H14	1600116														
									FINEBARK TEXTURED																
02	4								¼-20 RIVNUT, FLT. HD.	B.F. GOODRICH A25-80	1700014														
03	4								* 6-32 RIVNUT, CSK HD.	B.F. GOODRICH A6-106	1700037														
04																									
05																									
06	1					D	2636287		PANEL ASS'Y, RIGHT		2636287														
00																									

NOTES.

P/L 2636283

P.L. 2636283 REV ____ SHT 5 OF 13

DESCRIPTION TOP ASS'Y 3900 CHAMBER

NEXT ASSY END ITEM BY V. A. CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____ ____ ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC'D	FAB CD	PURCHASING PO NO.	QTY DUE	REC'S'D	MANUFACTURE ACT	EST ACT	HRS	COM	COM	PLATE/PAINT IN	OUT	AREA
00																									
01	1					D	2636287		PANEL, RIGHT SIDE .062 AL ALY	SHT. 3003-H14	1636287-001														
									FINEBARK TEXTURED																
02	7								*6-32 RIVNUT, CSK HD.		1700037														
03	3								*8-32 RIVNUT, CSK. HD.		1700005														
04																									
05																									
07	1					D	1636286	B	PANEL, LEFT		1636286														
08	1					D	2636290	D	PANEL ASS'Y, PARTITION		2636290														
00																									
00	REF					C	1636003	A	ARTWORK, PANEL ASS'Y.																
01	1					D	2636290	D	PANEL, PARTITION .062 AL ALY	SHT. 3003-H14	1636290-001														
									FINEBARK TEXTURED																
02	9								*6-32 RIVNUT, FLT. HD.	B.F. GOODRICH A6-75	1700003														
03	4								*8-32 RIVNUT, FLT. HD.	B.F. GOODRICH A8-75	1700004														
04																									
05																									
09	1					D	2600100	F	BEZEL ASS'Y		2600100														
00																									
01	1					D	2600100	F	ANGLE BEZEL	(M/F 1636292-001)	1600100-001														
02	1					B	1636292	B	ANGLE, BEZEL		1636292-001														
03	2					B	1636292	B	ANGLE, BEZEL		1636292-002														
04																									
05																									
10	1					A	1602967	D	VENT PLATE, OUTER		1500553														
11	1					A	1602968	D	GASKET, VENT		2400063														
12	1					B	1640309		WELD ASS'Y. - TUBE GUIDE		1640309-001														
00																									
01	1					B	1640309		PLATE 1.25 × 1.25 × .032	304-302 SST	1640309-101														
02	1					B	1640309		TUBE .50 O.D. × .028 WALL × 1.00	304-302 SST	1640309-102														
03																									
04																									
13	2					C	1635605	A	LATCH KEEPER		4100051														

NOTES:

P/L 2636283

P.L. 2636283 REV ____ SHT 6 OF 13

DESCRIPTION TOP ASS'Y 3900 CHAMBER

NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____ ____ ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING P.O. NO	QTY	DUE	REQ'D	MANUFACTURE ACT EST HRS	ACT COM	PLATE/PAINT IN	OUT	AREA
14	A/R				2	B	1600091	A	SHIM, KEEPER		1600091-002													
15	1					B	1635880	A	FLEXIDRIVE EXT. MOD.		1635880-001													
16	1								FLEXIDRIVE		1500455													
17	1					B	1635882	A	THERMOMETER 8"	1635882-002	2300011													
18	1					B	1600136	B	CUP THERMOMETER		1600136													
19	1					A	1600076	B	BUSHING THERMOMETER		1600076													
20	2					B	1600004	D	COVER, BLOWER		1600004													
21	8								SPACER		4100093													
22	4								FEET		1500419													
23	A/R								INSULATION, FIBERGLASS		2400025													
24	A/R								INSULATION, PRESSTITE		2400026													
25	2								PLUG (1¼ DIA HOLE)		1700142													
26	1								PLUG (½ DIA HOLE)		3600081													
27	A/R								SPONGE STRIP		2400126													
28	1					A	1636422		~~LABEL, PRESSURE SENSITIVE~~		1636422													
29	1								CIRCUIT BREAKER 120V (CB1)	AM2-A3-A20-3	1400008													
30	1					B	2602503	C	THERMOSWITCH ASSY. (S1)		2300004													
00																								
01	1								THERMOSTAT	VULCAN 1D1C2-4	2300004													
02	1					A	1600007	C	BRACKET		1600007													
03																								
04																								
31	1								LAMP, NEON (DS1)		1400082													
32	1					D	2621006	A	MOTOR, BLOWER (B1)	MULTI-USAGE	2621006-001													

NOTES: 2 USE ONLY AS REQ'D TO OPTIMIZE SEAL.

P/L 2636283

P.L. 2636283 REV — SHT 7 OF 13
DESCRIPTION TOP ASS'Y (3900)
NEXT ASSY END ITEM BY ARENA CK'D — APPD —

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO — S.O NO —
QTY — PROM DATE — ACT —
RUN * — MACH — — —

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING P.O. NO	QTY	DUE	REC	MANUFACTURE ACT	EST ACT	STD HRS	COM	COM	PLATE/PAINT IN	OUT	AREA
33	1					D	2621007	A	MOTOR, BLOWER (B2)	MULTI-USAGE	2621007																
34	1								RELAY (K1)		1400218																
35	1								CAPACITOR .05uf 400V (C1)		0700520-400																
36	2					B	2622524		HEATER ASS'Y (8.75 Ω)	(HR1, HR2)	2622524-001																
00																											
01	1					B	1635874		SHEET, HEATER		1635874																
02	4					B	1635868		STANDOFF, HEATER		1635868																
03	2								INSULATOR, CERAMIC	BIRNBACH #458	1500327																
04	2					B	2635875		ELEMENT 8.75 Ω		2635875-001																
00																											
01	1					B	2635875-001		ELEMENT, HEATER 8.75 Ω	LYON-RURAL ELECTRIC	2200003																
02	2				△3				STUD	BIRNBACH # 458	1500327																

NOTES: △3 ITEMS 2 & 3 (SHT. 8) ARE SEPARATED FROM STK. ITEM 1500327 AND SUPPLIED TO VENDOR. REMAINING ITEMS ARE RESHELVED.

P/L 2636283

P.L. 2636283 REV ____ SHT 8 OF 12

DESCRIPTION TOP ASSY. 3900 CHAMBER

NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO. ____ S.O. NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING PO NO	QTY DUE	REC'D	MANUFACTURE ACT STD HRS	EST ACT COM	COM	PLATE/PAINT IN	OUT	AREA
03	2					(3)	SEE SHT. 7		NUT	BIRNBACH # 458	1500327													
04																								
05	4					A	1695867	B	GASKET INSULATOR		1695067													
37	1					B	2618018	B	CO_2 ASS'Y, DUAL STEM (L1)	(4) (5)	2618018-001													
00																								
~~01~~	~~1~~					~~B~~	~~2618005~~		~~CO_2 VALVE WELDMENT ASS'Y.~~		~~2618005 001~~													
02	1					B	1647844		INJECTOR ASSY., CO_2 DUAL STEM		1647844-002													
00																								
~~01~~	~~1~~					~~C~~	~~1618012~~	~~B~~	~~MODIFICATION, PIPE PLUG~~	~~1618012 001~~	~~MF 3600078~~													
01	1					B	1647397		FITTING, INJECTOR	M/F 3600198	1647397-101													
02	1					B	1647841		TUBE, CO_2 INJECTOR	TYPE 300 SS 1/8 O.D., .020 I.D.	1647841-103													
03	1					B	1647841		TUBE, CO_2 INJECTOR	TYPE 300 SS 1/8 O.D., .020 I.D.	1647841-104													
04	1					B	1647841		TUBE, CO_2 INJECTOR	TYPE 300 SS 1/8 O.D. .020 I.D.	1647841-111													
05	1								FITTING, INJECTOR		3600197													
03	AR								INSULATION	PRESSTITE TYPE 5	2400026													
04	1					B	1647407		CO_2 VALVE & BRACKET ASS'Y.	MULTI-USAGE	1647407-001													
38	1								TERMINAL BLOCK (TB1)		1400572													
39	~~1~~					~~B~~	~~2635055~~		~~PANEL ASS'Y SIGNAL (A3)~~		~~2635055~~													
40	~~1~~					~~C~~	~~2695058~~		~~POWER PANEL ASS'Y (A2)~~		~~2695058~~													
41	1								PROBE (R1)		2300032													
42	~~1~~								~~OUTLET CONVENIENCE (U1)~~		~~1500083~~													

NOTES: (4) 3900R - USE 2618018-002

(5) CO_2 PSI OPTIONAL PER CUSTOMER PREFERENCE

P/L 2636283

PL 2636283 REV ____ SHT 9 OF 13
DESCRIPTION TOP ASS'Y 3900 CHAMBER
NEXT ASSY END ITEM BY ~~ARENA~~ CK'D ____ APPD ____

REV ECN DATE BY APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV.	DESCRIPTION	MFG OR MFG NO.	STOCK OR PART NO.	JOB QTY	AUX	QTY REC	FAB CD	PURCHASING PO NO	QTY DUE	REC'D	MANUFACTURE ACT EST HRS	ACT COM	COM	PLATE/PAINT IN	OUT	AREA
43	1				A	2635264	A	CABLE ASS'Y. (W1)		2635264-005														
00																								
01	A/R							WIRE, 18 AWG	COHU STOCK	7700618-999														
02	6							SOLDERLESS TERMINAL	(SPADE)	1500055														
03																								
04																								
44	1				A	2635265	B	CABLE ASS'Y. (W2)		2635265-005														
00																								
01	A/R							WIRE 14 AWG	COHU STOCK	7700614-999														
02	A/R							WIRE 18 AWG	COHU STOCK	7700618-999														
03	8							SOLDERLESS TERMINAL	(SPADE)	1500055														
04	2							SOLDERLESS TERMINAL	(SPADE)	1500054														
05																								
06																								
45	1				A	2635833		CABLE ASS'Y. 125V (W3)		2635833-003														
00																								
00	REF				D	1635841	A	SCHEMATIC DIAGRAM - 125V																
01	A/R							WIRE, TEFLON 14 AWG		1500380														
02	A/R							WIRE, TEFLON 18 AWG		1500387														
03																								
04	4							SOLDERLESS TERMINAL	(SPADE)	1500054														
05	2							SOLDERLESS TERMINAL	(SPADE)	1500055														
06	3							SOLDERLESS TERMINAL	(RING)	1500062														
07																								
08																								
~~46~~	~~1~~							~~FUSE 15A~~		~~1400037~~														
47	6							WIRE NUT, SMALL		1500188														
48	1							GROMMET ½"		1500032														
49	A/R							CABLE TIE		1500014														
50	A/R							PUSHMOUNT		1500013														
51	1				C	2619064		LN2 INJECTOR ASS'Y.		2619064-001														
00																								
01	1				C	2619064	B	MODIFIED CAP, SWIVEL	2619064-101	M/F 3600093														

NOTES:

P/L 2636283

PL 2636283 REV ____ SHT 10 OF 13

DESCRIPTION TOP ASS'Y 3900 CHAMBER

NEXT ASSY END ITEM BY ARENA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO. ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____ ____ ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING P.O NO	QTY	DUE	REC'D	MANUFACTURE ACT	EST	ACT	HRS	COM	COM	PLATE/ PAINT IN	OUT	AREA
02	2					C	2619064	B	TUBE, LN2 INJECTOR ASS'Y.	.125 O.D. × .016 WALL	2619064-102																
										SST 302-304																	
03																											
04																											
52	1								COUPLING, FLEXIDRIVE		4100003																
53	1								NUT		1500735																
54	2					A	1635610		SPACER		1635610																
55	4								* 4 × 1/2 PHP-SMS		6904122-400																
56	22								* 4 × 1/4 FHP-SMS		6904122-100																
57	2								* 4-40 × 5/8 PHP-MS		6804405-824																
58	2						1648659-101		SUPPORT BLOCK - INNER	LINER, 3900 & 5900	1648659-101																
59	30								* 6 × 1/2 PHP-SMS		6906112-400																
60	16								* 6-32 × 1/2 PHP-MS		6806321-224																
61	14								* 6 × 3/4 PHP-SMS		6906342-400																
62																											
63	4								* 8-32 × 3/8 PHP-MS		6808323-824																
64	13								* 8 × 1/2 OHP-SMS		6908122-200																
65	2								* 8-32 × 1/2 OHP-MS		6808321-222																
66																											
67	4								* 10-32 × 5/8 PHP-MS		6810325-824																
68	4								1/4-20 × 3/4 HEX-HC-MS		6814203-427																
69																											
70	5								* 6 SPLIT RING WASHER		6606011																
71	4								1/4-20 FLAT WASHER		6614001																
72	4								* 10 SPLIT RING WASHER		6610011																
73	2								GROMMET		1500026																
74																											
75	A/R								RTV 106	DOW-CORNING	2400003																
~~76~~	~~A/R~~								~~WIRE, TEFLON 14 AWG~~		~~1500380~~																
77	A/R								WIRE, TEFLON 18 AWG		1500387																
78																											
79	2								SOLDERLESS TERMINAL	(RING)	1500062																
80	2								SOLDERLESS TERMINAL	(RECER)	1500047																

NOTES:

P/L 2636283

P.L. 2636283 REV ____ SHT 11 OF 13

DESCRIPTION TOP ASS'Y (3900)

NEXT ASSY END ITEM BY BRAMA CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD.
SAN DIEGO, CALIF

JOB NO ____ S.O. NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____ ____ ____
____ ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	ALL	QTY REC	FAB CD	PURCHASING PO NO	QTY	DUE	REC	MANUFACTURE ACT STD	EST HRS	ACT COM	COM	PLATE/PAINT IN	OUT	AREA
81	1								SOLDERLESS TERMINAL	(RING)	1500055															
82	1								BUTCH PLUG .75 DIA HOLE x.935	OD.	3600081															
83	2								*10 SPLIT LOCKWASHER		6610010-000															
84	1								*10-32 x 3/4 PHP-MS		6810323-404															
85	4								*10 FLAT WASHER		6610000-000															
86	2								*10-32 HEX NUT		6710320-000															
87	5								*6 x 1/2 PHP-SMS		6906120-400															
88	1					C	2618020		SHIP KIT (SENT WITH 3900	CHAMBER)	2618020-001															
00																										
01	1								HOSE		3600123															
02	1								STRAINER		1400110															
03	1								NUT		3600120															
04	1								SLEEVE		3600121															
05	1								CONNECTOR		3600004															
06	1								CONNECTOR		3600119															
07	1								WASHER		3600122															
08																										
09																										
10																										
89	1								SOCKET (J1)		2000044															
90	1								TERMINAL BLOCK (TB2)		1400509															
91	1							⚠	CIRCUIT BREAKER 240V (CB1)	AM2-A3-A20-2	1400008															
92	4								*6-32 x 1/4 PHP-SMS		6906140-400															
93	2					A	2635048		CAPACITOR, MOD. (C2, C3)		2635048															
00																										
01	1								CAPACITOR		0800007															
02	1								SWAGE NUT		1700029															
03																										
94	1								STRAIN RELIEF		1500077															
95	8.5	FT.							POWER CORD		1500394															
96	1								PLUG, POWER 120V		2000135															
97	4								SOLDERLESS TERMINAL	(RING)	1500071															
98	1								SOLDERLESS TERMINAL	(RING)	1500056															

NOTES:

P/L 2636283

P.L. 2636283 REV ____ SHT 12 OF 13
DESCRIPTION TOP ASS'Y 3900 CHAMBER
NEXT ASSY END ITEM BY Apuna CK'D ____ APPD ____

REV ECN DATE BY APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO. ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY B QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV.	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC'D	FAB CD	PURCHASING P.O. NO	QTY DUE	REC'D	MANUFACTURE ACT EST HRS	ACT COM	COM	PLATE/PAINT IN	OUT	AREA
99	A/R								WIRE, TEFLON 12 AWG		1500376													
100	2								* 6-32 HEX NUT		6786322													
101	A/R								WIRE, HIGH TEMP 12 AWG	12958/J853LG5-1	1501414													
102	1						⚠1		PLUG, POWER 240V	HUBBLE 4570-C	2000224													
103	1					A	1600012	C	NULL, TERMINAL COVER		1600012													
~~104~~	~~1~~								~~PLUG (P2)~~		~~2600409~~													
105	2								* 6-32 × 3/4 PHP-MS		6806323-404													
106	2								* 4 × 1/4 PHP-SMS		6904140-400													
107	1					B	1643476		IDENT. PLATE		1643476													
108	1					B	2618017	B	CO_2 ASSY. (300 PSI) DUAL STEM	⚠6 ⚠7	2618017-001													
00																								
101	~~1~~					B	~~2618005~~		~~CO_2 VALVE WELDMT ASSY~~		~~2618005-002~~													
02	1					B	1647844		INJECTOR ASSY, CO_2 DUAL STEM		1647844-001													
00																								
01	1					B	1647397		FITTING, INJECTOR	M/F 360013E TYPE 304 SS 1/8 O.D. .035 I.D.	1647397-101													
02	1					B	1647842		TUBE, CO_2 INJECTOR	TYPE 300 SS 1/8 O.D. .035 I.D.	1647842-103													
03	1					B	1647842		TUBE, CO_2 INJECTOR		1647842-104													
04																								
03	A/R								INSULATION	PRESSTITE TYPE S	2400026													
04	1					B	1647407		CO_2 VALVE + BRACKET ASSY	MULTI-USAGE	1647407-002													
109						B	2600409		PLUG MOD. P2															
00																								
01	1								PLUG, 4 PIN AUDIC	AMPHENOL 91 MC4M	2000051													
02	1								CHAIN, 4"		1500226													

NOTES:
⚠6 CO_2 PSI OPTIONAL PER CUSTOMER PREFERENCE
⚠1 3900R (300 PSI) USE 2618017-002

P/L 2636283

P/L 2636283 REV ____ SHT 13 OF 13

DESCRIPTION TOP ASSY 3900 CHAMBER

NEXT ASSY END ITEM BY ____ CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____ ____ ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	ALL	QTY REC	FAB CD	PURCHASING PO NO	QTY	DUE	REC	MANUFACTURE ACT STD	EST HRS	ACT COM	COM	PLATE/PAINT IN	OUT	AREA
03	2								#6 EYELET		3600101															
04	1								# 2-56 X 5/32 PHP-MS																	
05	A/R								WIRE 20GA. BUS																	
06	1								#2 FLAT WASHER		6602000006															
07																										
00	REF				△1	D	1640083		CO_2 TO LN_2 WITH REDUNDANT VALVE		1640083-001															
00	REF				△1	D	1640083		CO_2/LN_2 DUAL WITH REDUNDANT VALVE		1640083-002															
110																										
111																										
112																										
113	1					B	1650205		COVER, CUTOUT		1650205-101															
114																										
115	2								#4 40 x 3/8 PHP-MS		6804403-804															
116	2								#4 SPLIT LOCKWASHER		6604010															
117	2								#4-40 HEX NUT		6704400-001															
118																										
119																										
120	REF					D	1650240		CHAMBER, TYPE V CONTROLLER RETROFIT △8		1650240-001															
00																										
01	REF					D	1650223		INTERCONNECT ASSY TYPE V CONTROLLER △8		1650223-001															
									- MULTI-USAGE -																	

NOTES: △8 THESE DRAWINGS & P/L TOGETHER MAKE UP THE RETROFIT KIT!

P/L 2636283

REVISIONS			
ZONE	LTR	DESCRIPTION	DATE	APPD

—INSTRUCTIONS FOR CHAMBER RETROFIT— TYPE V CONTROLLER

1. REMOVE CHAMBER RIGHT SIDE PANEL TO ALLOW ACCESS TO CONTROLLER & PROBE GUIDE TUBE. ON MODELS 2850, 5900 & 7650 TOP PANEL MUST BE REMOVED AS WELL.
2. REMOVE EXISTING CONTROLLER & ITS PROBE. DO NOT DESTROY BLACK PRESS-TITE.
3. NOTE CHAMBER REAR PANEL CONFIGURATION & DECIDE WHICH MEANS OF MOUNTING THE REMOTE INTERFACE CABLE ASSY. PLUG BEST SUITS YOUR CHAMBER & REQUIREMENTS →
4. MAKE THE REAR PANEL MODIFICATIONS
5. MOUNT THE REMOTE INTERFACE CABLE ASSY PLUG TO THE REAR PANEL— SEE DRAWING D1650223 & PARTS LIST FOR CABLE & HARDWARE CALLOUTS
6. INSERT THERMOCOUPLE ASSY IN PROBE GUIDE TUBE & SECURE IN PLACE USING BLACK PRESS-TITE—SEE DRAWING D1650223 —CAUTION—DO NOT SHORTEN THERMOCOUPLE ASSY WIRE FOR ANY REASON
7. INSTALL TYPE V CONTROLLER & WIRE PER WIRING DIAGRAM D1643470 OR D1643471 SHEET 2 OF 2. IF NECESSARY, COIL EXCESS THERMOCOUPLE WIRE & POSITION IT BETWEEN CONTROLLER & CHAMBER TO ACT AS A SERVICE LOOP IF NEEDED
8. REPLACE TOP PANEL IF YOU HAVE A MODEL 2850, 5900 OR 7650
9. BEFORE REPLACING SIDE PANEL SEE CONTROLLER MANUAL FOR SET UP & CALIBRATION PROCEDURES
10. CALIBRATE CONTROLLER
11. REPLACE SIDE PANEL

MODEL 3900 REAR PANEL CONFIGURATIONS— MODIFY BY ADDING CUTOUT AT DIMENSIONS SHOWN



1/2 SCALE



1/2 SCALE

1. REMOTE INTERFACE CABLE ASSY PLUG CUTOUT DIMENSIONS:



⚠ FINISH (IF APPLICABLE)

⚠ MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

						ENGINEERING ACTIVITY	DELTA DESIGN INC.
						M1947	
						DESIGN	TITLE: CHAMBER, TYPE V CONTROLLER RETROFIT 3900
						DRAFTING OLENIK 12-21-X	
						CHECKING	
						APPROV	SIZE D — DWG NO. 1650240
						RELEASE	
						DO NOT SCALE DWG	SCALE — SHEET — OF —
						MATERIAL ⚠	
						FINISH ⚠	

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPD



5 36" LONG CABLE USED WITH MODEL 7650
28' LONG CABLE USED WITH ALL OTHER MODELS

6 FINISH (IF APPLICABLE)

6 MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

	-	2635573	9145				
	-	2636342	6419				
	-	2635601	5900				
	-	2636603	5900				
	-	2605402	5900				
	-	2605110	7300				
QUANTITY	NEXT ASSY	USED ON	SERIAL NO.	DATE EFF	DWG REV	MATERIAL 6	
APPLICATION			EFFECTIVITY			FINISH 6	

ENGINEERING ACTIVITY

DESIGN	
DRAFTED	CLF JWK 11-29-84
CHECKED	
APPROV	
RELEASE	
DO NOT SCALE DWG	

DELTA DESIGN INC.
A SUBSIDIARY OF ORBIT INC.
SAN DIEGO, CA. 92186

TITLE:
INTERCONNECT ASSY.
TYPE V CONTROLLER WITH
IEEE-488

SIZE	CODE IDENT	
D		1650223

SCALE | SHEET

P.L. 1650223 REV ____ SHT 1 OF 1

DESCRIPTION INTERCONNECT ASSY TYPE V CONTROLLER WITH IEEE-488

NEXT ASSY MULTI-USAGE BY F.J.O. CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO ____ S.O. NO. ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING PO NO	QTY DUE	REC'D	MANUFACTURE ACT EST ACT HRS. COM COM	PLATE/PAINT IN	OUT	AREA
00	X					D	1650223		INTERCONNECT ASSY- TYPE V CONTROLLER WITH IEEE-488		1650223-001											
00																						
00																						
00																						
00																						
00																						
00																						
01	REF					D	1650160		TYPE V CONTROLLER		1650160-001											
02	1								PROGRAM INTERCONNECT CABLE													
03	1								IEEE-488 INTERFACE CABLE													
04	1								JACK SOCKET ASSY.	ANSLEY #609-003	1700324											
05																						
06																						
07	1					B	1650230		THERMOCOUPLE ASSY	MULTI-USAGE	1650230-001											

NOTES:

1650223
P/L

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPD
	A	PER ECN M2052 THAMES 6-18-80 TABULATION .002 8.27 WAS 5.12	8-15-80	



DASH NO.	"A" DIM	"B" DIM	USED ON
-001	44.4"	5.25"	2300 THR. 7650, 2850A
-002	96.0"	5.25"	8000
-003	30.0"	8.27"	2300A

4 REMOVE ALL BURRS & SHARP EDGES FROM I.D. OF ITEM 1 (BOTH ENDS)

3 INSURE ITEM 5 IS SOLIDLY CRIMPED OVER ITEM 4 — THEN ITEM 2 IS CRIMPED OVER ITEM 5

FINISH (IF APPLICABLE)

MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED

DASH	QTY	NEXT ASSY	USED ON
002	1	1650223	REF
001	1	1650223	

APPLICATION

SERIAL NO. | DATE EFF | DWG REV

EFFECTIVITY

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS .XX ± .03, .XXX ± .010
ANGLES 0° 30'
HOLE TOLERANCES
.013 THRU .125 +.004 -.001
.126 THRU .250 +.005 -.001
.251 THRU .500 +.006 -.001
.501 THRU .750 +.008 -.001

MATERIAL 1
FINISH 2

ENGINEERING ACTIVITY M1952

DESIGN	
DRAFTED	OLF JMK 12/6/79
CHECKED	
APPROV	
RELEASE	

DO NOT SCALE DWG

DELTA DESIGN INC.
A SUBSIDIARY OF CONTROL DATA CORP.
SAN DIEGO, CA. 92138

TITLE: THERMOCOUPLE ASSY.

SIZE B | CODE IDENT | 1650230

SCALE | SHEET 1 OF 1

P.L. 1650230 REV ____ SHT 1 OF 1
DESCRIPTION THERMOCOUPLE ASSY.
NEXT ASSY MULTI USAGE BY F.J.O. CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO. ____ S.O NO. ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO	STOCK OR PART NO.	JOB QTY	AUL	QTY REC	FAB CD	PURCHASING P.O. NO	QTY DUE REC	MANUFACTURE ACT EST ACT STD HRS COM COM	PLATE/PAINT IN OUT	AREA
00	X					B	1650230		THERMOCOUPLE ASSY.		1650230-001									
00		X				B	1650230		THERMOCOUPLE ASSY		1650230-002									
00			X			B	1650230		THERMOCOUPLE ASSY		1650230-003									
00																				
00																				
00																				
00																				
01	1	1				B	1650230		TUBE, ALUMINUM		1650230-101									
									3/16 O.D. X .022 WALL X 5 1/4 LONG											
02	1	1	1			B	1650230		TUBE, ALUMINUM		1650230-102									
									3/16 O.D. X .022 WALL X .20 LONG											
03	1	1	1						COLLAR, SET SCREW	BFRG # CS5	1700292									
04	4'								WIRE, THERMOCOUPLE	IRON CONSTANTAN	1501375									
		8'							" "	" "	1501375									
			30"						" "	" "	1501375									
05	1	1	1						QUIKTIP	# 128543	1700327									
06			1				B1650230		TUBE, ALUMINUM		1650230-103									
									3/16 O.D. X .022 WALL X 8.27" LONG											

NOTES:

P/L 1650230

ZONE	LTR	DESCRIPTION	DATE	APPD



DASH	QTY	NEXT ASSY	USED ON	SERIAL NO.	DATE EFF	DWG REV
		1650160				
		A998		120		N/C

APPLICATION | EFFECTIVITY

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
TOLERANCES ON
DECIMALS: .XX ±.03, .XXX ±.010
ANGLES: 0°30'
HOLE TOLERANCES

MATERIAL ⚠
FINISH ⚠
DO NO SCALE DWG

ENGINEERING ACTIVITY

DESIGN	JC SYSTEMS INC
DRAFTED	" 22 JUNE 1970
CHECKED	
APPROV	
RELEASE	

ENTERPRISES
SAN DIEGO, CALIFORNIA

TITLE: PRINTED CIRCUIT P.C. SCH- TEMPERATURE DIAL-SWITCH II MODEL A998

SIZE	CODE IDENT	
B		997

SCALE N.A. | 1649548 | SHEET 1 OF 1

⚠ FINISH (IF APPLICABLE)

⚠ MATL (IF APPLICABLE)

NOTES: UNLESS OTHERWISE SPECIFIED


REVISIONS
ZONE | LTR | DESCRIPTION | DATE | APPD
-SEE SCH D969 SHT 1 OF 2
C1 HEAT & COOL JUMPERS WERE DEVISED
CKT COMP (SHOWN)
R24 "AMBIENT" 3299-P-202
R9 "SLOPE" 3299-P-203
R11 "BALANCE" 3299-P-203
Q1-AD590K THERMOCOUPLE TYPE "J"
BOND WITH 5 MIN EPOXY
THERMALLOY HEAT SINK 6070B, 6071B, 6107-14 (1 EA)
TB1 KULKA 410-4
PROBE
Z15 4310R-101-223
P5 (REMOTE SETPOINT) 609-2627
Z16 SN74126N
Z11 8243 (OPT)
Z14 4310R-101-223
Q1 UA1305
Z4 INTERSIL CL 7109 12 BIT BINARY A/D CONV.
Z1 INTEL 8748 MICROPROCESSOR
XTAL 1 3.58 MHZ
Z13 4310R-101-223
P4 (SET POINT) 609-2027
Z10 8243
Z12 4310R-101-223
P3 (DISPLAY) 609-2627
Z9 8243
Q2 UA7905
Q3 TIC 236D
K2 1A5AHH
K3 1A5AHH
K3 1A5AHH
4002(6)
C24 220uf 25V
C22 8000uf 15V
F1 5A.
TB2
18 REMOVE
16 SELECT COM
15 NULL
14 +5V.
13 GND
12 GND XFORMER CT
11 AC-1
10 AC-2
AC INPUT
9 FULL WAVE OUT
8 NULL 1
7 NULL 2
RELAY CONTACTS
6 HEAT 1
5 HEAT 2
RELAY CONTACTS
4 COOL
3 SØH (115V)
2 COOL
1 HEAT
HEAT JUMPER
COOL JUMPER
THERMALLOY HEAT SINK 6070B/6071B (1 EA)
P1 OPT NORMALLY LEFT OFF 609-1627
FACTORY SELECT JUMPERS "A" THRU "F" FARSIDE ASSY
-JUMPER "A" IS INSTALLED FOR +175° C SETPOINT LIMIT
-LEFT OFF FOR 315°C LIMIT
WHEN "P1" & "CR1" IS NOT USED, INSTALL JUMPERS "A" THRU "D"
F.A. RESISTORS R22B, R25B, R27B, & R28B. WHEN INSTALLING F.A. RES. "B" LOCATE "PIGGI-BACK" STYLE
FINISH (IF APPLICABLE)
MATL (IF APPLICABLE)
NOTES: UNLESS OTHERWISE SPECIFIED
ENGINEERING ACTIVITY
DESIGN J.C SYSTEMS INC
DRAFTED 09 MAY 1979
CHECKED
APPROV
RELEASE
DO NOT SCALE DWG
DELTA DESIGN INC.
A SUBSIDIARY OF CONIC INC.
SAN DIEGO, CA. 92138
TITLE: PRINTED CIRCUIT BD ASSY - TYPE V TEMPERATURE CONTROLLER MODEL A970
SIZE D
CODE IDENT
970
SCALE 2/1
1044528
SHEET 1 OF 1
END ITEM
ON
NC
DASH NEXT ASSY
USED ON
SERIAL NO.
DATE EFF
DWG REV
MATERIAL
APPLICATION
EFFECTIVITY
FINISH


REVISIONS
ZONE LTR DESCRIPTION DATE APPD
A ADDED JUMPER "A" - "D"
B ADDED "TØ & INT" FROM P1-5 & 10 TO P5-22 & 24
C ADDED POT R35, Z16, TP7 TPB R36 & R34, FA. RES. R22B, R25B, R27 & R28 CALIBRATION SPECS. REMOVED R21-P01
-5 GUARD PLANE
-5V GUARD PLANE
P1 ANSLEY (OPT) 609-1627
Z1 INTEL 8748
Z4 ICL 7109
CD4030BE
CD4093BE
IN914
IN827
AD590K
TYP PIN OUT FOR μA714 (Z5-Z8)
A = ANALOG SECTION
D = DIGITAL SECTION
TO SHT 2
(SHT 2) Z9-6
P2 "INTRABUS"
PORT 2
GND
D/B
FINISH (IF APPLICABLE)
MATL (IF APPLICABLE)
NOTES: UNLESS OTHERWISE SPECIFIED
ENGINEERING ACTIVITY
DESIGN J C SYSTEMS INC
DRAFTED 09 MAY 1979
CHECKED
APPROV
RELEASE
DO NOT SCALE DWG
DELTA DESIGN INC.
TITLE PRINTED CIRCUIT BD SCH - TYPE X TEMPERATURE CONTROLLER MODEL A970
SIZE D
CODE IDENT
969
SCALE N A
1644550
SHEET 1 OF 2


REVISIONS
ZONE LTR DESCRIPTION DATE APPD
+5V
Z12 22K RES PAC BOURNS 4310R-101-223
Z13 22K RES PAC BOURNS 4310R-101-223
C28 .1mf
C29 .1mf
(OPTIONAL) Z15 22K RES PAC BOURNS 4310R 101-223
(OPTIONAL) Z14 22K RES PAC BOURNS 4310R-101-223
ANSLEY P4 609-2027
SET POINT BCD SW. INTERFACE
TENTHS
UNITS
TENS
HUNDREDS
SIGN+ - U
GND
Z10 8243
Z11 8243
P5 ANSLEY (OPTIONAL) 609-2627
REMOTE TEMP PROGRAM (OPTIONAL)
SIGN U = +
NULL U + AT TEMP
READ TEMP
REMOTE CONTROL
SET POINT VALID
P3 ANSLEY 609-2027
DISPLAY INTERFACE
D0
D1
D2
D3
D4
D5
D6
D7
LOW NIBBLE DEC POINT
HIGH NIBBLE DEC POINT
DIGIT PAIR 2 STROBE
DIGIT PAIR 1 STROBE
Z9 8243
C27 .1mf
DISPLAY CS
PROG
SET POINT CS
A
B
C
D
TO SHT 1
P1-9
P1-10
P5 TB2
FULL WAVE OUT
AC-1
AC-2
IN
XFORMER CT GND
A7805C
A7905C
C19 220 10V
C20 .1mf
C21 220 10V
C22 8000 15V
C23 .1mf
C24 220 10V
C25 .1mf
CR4
CR5
CR6 (6) IN4002
CR7
CR8
CR9
R35 10K
R34 10K
SN74126N
CR11 IN914
CR10 IN914
K2 IASAHH
K1 IASAHH
CR12 IN914
K3 IASAHH
R30 3.3K
C26 .04mf 500V
T1C2360
Q4
R32 270
R31 680
COOL
SØH
F1 5A
TB2
N.C
SELECT COM
REMOTE NULL
COOL
HEAT
NULL
HEAT
GND
FINISH (IF APPLICABLE)
OPTIONAL JUMPER NORMALLY LEFT OUT
NOTES: UNLESS OTHERWISE SPECIFIED
ENGINEERING ACTIVITY
DESIGN J.C SYSTEMS INC
DRAFTED 03 MAY 1979
CHECKED
APPROV
RELEASE
DO NOT SCALE DWG
DELTA DESIGN INC.
TITLE: PRINTED CIRCUIT BD SCH - TYPE V1 TEMPERATURE CONTROLLER MODEL A 970
SIZE D
CODE IDENT
969
SCALE N.A
1644550
SHEET 2 OF 2
A970
1 of CN
BASIC QTY
NEXT ASSY
USED ON
APPLICATION
SERIAL NO.
DATE EFF
DWG REV
EFFECTIVITY
MATERIAL
FINISH

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPROVED
	A	ADDED ITEM NO PER ECN M030	10-11-72	L. ELLIS 10-27-72
	B	ADDED ITEM 10. PER ECN M061 Haun 11-9-72	11-9-72	L ELLIS
	C	PER ECN M191 R Brooks 3-7-73 ADDED CR1, ITEM 11	3-24-73	ADesai
	D	PER ECN M385 DTD 9/24/73 FJO ADDED CR2 (1N4004)	9/24/73	A. Desai
	E	PER ECN M617 DATED 4/18/74 - GK+ ADDED Q2(2N3565), CR3 (IN4004), Q1 WAS 40716	4/18/74	
	F	PER ECN M739 R Brooks 6-21-74 SEE ECN FOR CHANGE		N.B.M 6-28-74



P/L "A" SIZE

QTY REQ'D	NOMENCLATURE OR DESCRIPTION	CODE IDENT	IDENTIFYING NUMBER	SPECIFICATION	MATERIAL OR NOTE	ITEM NO

1) ENG. REF: 15 AMPS RESISTIVE MAX. CURRENT RMS
2.) SCHEMATIC REF: C1635446
3. RCA 40716 IS A SUBSTITUTABLE PART FOR ITEM 5 RCA T4706D

NOTES.

MULTI. USAGE				
—	A1161	TYPE III 140V		
—	A1160	TYPE III 120V		
NEXT ASSY	USED ON	SERIAL NOS	DATE EFF	DWG REV LTR
APPLICATION		EFFECTIVITY		

UNLESS OTHERWISE SPECIFIED THE FOLLOWING APPLIES
BREAK ALL SHARP EDGES .005
MAX SURFACE ROUGHNESS 32 RMS
THDS INT CL 2B EXT CL 2A
DIMENSIONS ARE IN INCHES
TOLERANCES ON
FRACTIONS ± 1/64 ANGLES ± ½°
DECIMALS XX ± .010
XXX ± .005

MATERIAL ~

FINISH ~

	BY	DATE
DESIGN	M.W.TYLER	2-16-72
DRAFTED	M.W.TYLER	2-16-72
CHECKED	[illegible]	5-1-72
APPROV	L. ELLIS	10-27-72

DO NOT SCALE DRAWING

PART NO. 2635445

DELTA DESIGN INC.
8000 FLETCHER PKWY
LA MESA CALIF 92041
TEL A/C (714) 465 4141

TITLE: 120/240V TRIAC ASS'Y

SIZE	CODE IDENT NO	DRAWING NO	REV LTR
C		2635445	F

SCALE 2:1 SHEET 1 OF 1

BLUE CARD

PL 2635445 REV ____ SHT 1 OF 1

DESCRIPTION IRIAC ASSY 120/240 VOLT

NEXT ASSY END ITEM BY ____ CK'D ____ APPD ____

REV	ECN	DATE	BY	APP

DELTA DESIGN
5725 KEARNY VILLA RD
SAN DIEGO, CALIF

JOB NO. ____ S.O. NO ____
QTY ____ PROM DATE ____ ACT ____
RUN * ____ MACH ____

ITEM NO	ASSY & QTY -001	-002	-003	-004	INDENTURE	SIZE	DRAWING NO.	REV	DESCRIPTION	MFG OR MFG NO.	STOCK OR PART NO.	JOB QTY	ALL	QTY REC	FAB CD	PURCHASING P.O. NO	QTY DUE	REQ'D	MANUFACTURE ACT	EST ACT	HRS	COM	COM	PLATE/PAINT IN	OUT	AREA
00	X				C	2635445		TRIAC ASSY 120/240	VOLT	2635445-001															
00	REF				C	1635446		SCHEMATIC 120/240	VOLT TRIAC																
00	REF				B	1635443		ARTWORK 120/240 VOLT TRIAC																	
01	1				C	1635444		P.C. BOARD 120/240	VOLT TRIAC	1635444-101															
02																									
03	1							INTEGRATED CIRCUIT Z1	RCA CA3079	1000026															
04																									
05	1							TRIAC Q1	RCA T4706B ⚠1	124706															
06	1							TRANSISTOR Q2	2N3565	1203565															
07	1							CAPACITOR 100 uf	12V C1 SPRIGUE	0510147-051															
08	3							DIODE CR1, CR2, CR3	IN4004	1104004															
09																									
10	1							RESISTOR, 1.2K, 1/4W, 5% R1		4045000-122															
11	1							RESISTOR, 8.2K, 1/4W, 5% R2		4045000-822															
12	1							RESISTOR, 4.7K, 1/4W, 5% R3		4045000-472															
13	2							RESISTOR, 10K, 2W 5% R4, R5		0310032-103															
14																									
15	1							SOCKET, I/C 14 PIN		1710283-001															
16	1				B	1603051		HEAT SINK		1500351															
17																									
18	2							6-32 x 1/2 PHP-MS-	SST	6806321-204															
19	2							#6 LWT-SST		6606020															
20	2							6-32 HN-SST		6706320															
21	2							STANDOFF, HEAT SINK		1500329															

NOTES:

⚠1 RCA 40716 MAY BE SUBSTITUTED FOR ITEM 5.

P/L 2635445

REVISIONS				
ZONE	LTR.	DESCRIPTION	DATE	APPROVED
	A	ECN CHANGE PER M030	10-11-72	L. ELLIS 10-27-72
	B	PER ECN M131 R Brooks 3-7-73 ADDED CR1 (IN4007) REMOVED CONNECTION OF Z1 PIN 14 TO 13	9-24-73	A. Desai
	C	PER ECN M385 DTD 9/24/73 E.I.O. ADDED CR2 (IN4004)	9/24/73	A. Desai
	D	PER ECN M617 DATED 4-18-74 - GKJ - ADDED Q2 (2N3565), CR3 (IN4004) Q1 WAS 40716	4/18/74	Kamin
	E	PER ECN M739 R Brooks 6-20-74 ADDED NOTE 2 & Q1 WAS T4706B		W. Ball 6-28-74



QTY. REQ'D	NOMENCLATURE OR DESCRIPTION	CODE IDENT.	IDENTIFYING NUMBER	SPECIFICATION	MATERIAL OR NOTE	ITEM NO.

⚠ RCA PART NO. 40716 IS A SUBSTITUTABLE PART FOR Q1 RCA T4706D

1. ALL RESISTORS 1/4W, 5%, CARBON.

NOTES: UNLESS OTHERWISE INDICATED.

NEXT ASSY.	USED ON	SERIAL NOS.	DATE EFF.	DWG. REV. LTR.
2635445	A1160 & A1161			

APPLICATION — EFFECTIVITY

UNLESS OTHERWISE SPECIFIED THE FOLLOWING APPLIES:
BREAK ALL SHARP EDGES .005
MAX. SURFACE ROUGHNESS 125 RMS
THDS. INT. CL. 2B, EXT. CL. 2A
DIMENSIONS ARE IN INCHES
TOLERANCES ON
FRACTIONS ± 1/64 ANGLES ± ½°
DECIMALS .XX ± .010
.XXX ± .005

MATERIAL: ~

FINISH: ~

	BY	DATE
DESIGN	J.C. ENT.	2-14-72
DRAFTED	M. LM. TYLER	2-16-72
CHECKED	[illegible]	5-1-72
APPROV.	L. ELLIS	10-19-72

DO NOT SCALE DRAWING

PART NO. ~

DELTA DESIGN INC.
8000 FLETCHER PKWY.
LA MESA, CALIF. 92041
TEL: A/C (714) 465-4141

TITLE: : SCHEMATIC — : 120/240V TRIAC

SIZE	CODE IDENT. NO.	DRAWING NO.	REV. LTR.
C		: C1635446	E

SCALE NONE — SHEET 1 OF 1

BLUE CARD

www.manualsplus.com
1018202